

Bid Sheet

ROOF REPLACEMENT PROJECT

Hawthorn Elementary
& Bus Barn
Camdenton R-III School District
172 Dare Blvd
Camdenton, MO 65020

We, the undersigned, propose to furnish all materials, labor, permits, licenses, and supplies to perform all work necessary and incidental to the partial reroofing of Hawthorn Elementary and Bus Barn for Camdenton R-III School District.

1. **Base Bid #1:** Install new fully adhered EPDM rubber roofing system and new sheet metal as specified.

Hawthorn Elementary \$ 51,831.00

Bus Barn \$ 19,411.00

Total Base Bid \$ 71,242.00

2. **Alternate #1:** Supply owner with a payment and performance bond in an amount equal to the sum of the contract.

Alternate #1 Amount \$1,230.00

3. **Unit Price: To remove and replace wet or damaged 2" thick insulation.**
Unit Price \$ 1.50 per square foot

Contractor shall state work schedule intentions by filling in the following information:

Number of calendar days to start project after receipt of contract 15 days.

Number of calendar days to complete project after receipt of contract 75 days.

Date: May 6, 2013

Submitted by: Missouri Builders Service, Inc.
P.O. Box 104205, Jefferson City, MO 65110


Print Name and Title: Dan Henley, Vice President

Signed by: Dan Henley, P.
(Must be signed by an Authorized Principal of the Company)

For office use only!

Bid # : _____

Date submitted: _____



MISSOURI BUILDERS SERVICE, INC.

ROOFING • SHEET METAL

3807 ROUTE CC • P.O. BOX 104205 • JEFFERSON CITY, MO. 65110-4205
PHONE – 573-636-7733 FAX – 573-636-7836

May 6, 2013

Camdenton R-III Schools
PO Box 1409
Camdenton, MO 65020

PROPOSAL

We propose to furnish and apply all necessary labor and equipment required to complete the work in a neat and satisfactory manner as stated below:

Hawthorn Elementary – Roof Area No. 2 (approximately 5,302 SF)

1. Remove existing rubber roofing and recovery board down to existing gravel surfaced asphalt built-up roofing. Spud down and remove existing gravel surfacing. Remove abandoned curbs and patch openings.
2. Adhere ½" Carlisle Securshield HD recovery board over existing asphalt roof in full coverage Flexible Fast adhesive. Install tapered insulation crickets at North wall between roof drains.
3. Fully adhere "Carlisle Fleeceback 115" EPDM rubber roofing over recovery board in full coverage Flexible Fast adhesive.
4. Adhere EPDM up and over top of perimeter walls and install new prefinished metal fascia.
5. Flash all equipment curbs, pipes and penetrations per manufacturer's instructions.
6. Install rubber walkpads on service side of all roof top units.
7. Upon completion furnish manufacturer's 15 year Total Systems, No Dollar Limit, Labor and Material warranty.
8. Comply with prevailing wage law set forth by the Missouri Department of Labor and Industrial Relations for the County of Camden, Missouri.
9. Sales Tax on materials is not included in bid price. Owner to provide copy of Tax Exempt letter and Project Exemption Certificate for contractors use to purchase materials for this project.

PRICE: \$51,831.00

This bid is limited to acceptance within 60 days from date unless withdrawn by written notice prior to this period. The company carries Workmen's Compensation and Public Liability Insurance. The company agrees to commence applications of above work with reasonable promptness, but shall not be liable for delays caused by uncompleted preliminary work, abnormal weather conditions, strikes or other labor trouble, unavailability of materials, interruption of transportation, acts of providence or any other reason beyond our control. Return trips necessitated by unfinished preliminary work while our work was being performed or because of damage to completed work by others after work is completed, will be subject to an extra charge. No back charges against this company will be approved unless they are presented to us and agreed upon before the work involved is performed.

Payment for same to be monthly progress payments and in full upon completion.

(Company or Institution)

By _____

Date: _____

Missouri Builders Service, Inc.

By 
Dan Henley

Date: May 6, 2013



MISSOURI BUILDERS SERVICE, INC.

ROOFING • SHEET METAL

3807 ROUTE CC • P.O. BOX 104205 • JEFFERSON CITY, MO. 65110-4205
PHONE – 573-636-7733 FAX – 573-636-7836

May 6, 2013

Camdenton R-III Schools
PO Box 1409
Camdenton, MO 65020

PROPOSAL

We propose to furnish and apply all necessary labor and equipment required to complete the work in a neat and satisfactory manner as stated below:

Bus Barn – West Addition (approximately 3,197 SF)

1. Remove existing rubber roofing to expose existing insulation.
2. Replace wet or damaged insulation with new insulation as needed per unit price per square foot.
3. Fully adhere “Carlisle Fleeceback 115” EPDM rubber roofing over existing insulation in full coverage “Flexible Fast” polyurethane adhesive.
4. Flash all equipment curbs, pipes and penetrations per the manufacturer’s instructions.
5. Install rubber walkpads on service side of roof top units.
6. Install new 24 gauge prefinished metal fascia at perimeters.
7. Upon completion furnish manufacturer’s 15 year Total Systems, No Dollar Limit, Labor and Material warranty.
8. Comply with prevailing wage law set forth by the Missouri Department of Labor and Industrial Relations for the County of Camden, Missouri.
9. Sales Tax on materials is not included in bid price. Owner to provide copy of Tax Exempt letter and Project Exemption Certificate for contractors use to purchase materials for this project.

PRICE: \$19,411.00

Unit Price

To remove and replace wet or damaged 2” thick insulation\$1.50 per square foot.

This bid is limited to acceptance within 60 days from date unless withdrawn by written notice prior to this period. The company carries Workmen’s Compensation and Public Liability Insurance. The company agrees to commence applications of above work with reasonable promptness, but shall not be liable for delays caused by uncompleted preliminary work, abnormal weather conditions, strikes or other labor trouble, unavailability of materials, interruption of transportation, acts of providence or any other reason beyond our control. Return trips necessitated by unfinished preliminary work while our work was being performed or because of damage to completed work by others after work is completed, will be subject to an extra charge. No back charges against this company will be approved unless they are presented to us and agreed upon before the work involved is performed.

Payment for same to be monthly progress payments and in full upon completion.

(Company or Institution)

By _____

Date: _____

Missouri Builders Service, Inc.

By Dan Henley
Dan Henley

Date: May 6, 2013